

ON LAGRANGIAN CONCORDANCE OF LEGENDRIAN KNOTS

BAPTISTE CHANTRAINE

ABSTRACT. In this article we define Lagrangian concordance of Legendrian knots, the analogue of smooth concordance of knots in the Legendrian category. In particular we study the relation of Lagrangian concordance under Legendrian isotopy. The focus is primarily on the algebraic aspects of the problem. We study the behavior of the classical invariants under this relation, namely the Thurston-Bennequin number and the rotation number, and we provide some examples of non-trivial Legendrian knots bounding Lagrangian surfaces in D^4 . Using these examples, we are able to provide a new proof of the local Thom conjecture.

1. INTRODUCTION

A contact structure ξ on a 3-manifold M is a completely non-integrable 2-plane field (i.e. it is locally defined as the kernel of a 1-form α such that $\alpha \wedge d\alpha \neq 0$). Throughout this paper M will be oriented and the contact structure will be assumed to be positive and transversally orientable. Transversally orientable means that the 1-form α can be globally defined and the positivity condition means that $\alpha \wedge d\alpha > 0$ (note that this really a condition on the contact structure and not the 1-form defining it). The completely non-integrable condition implies that any surface embedded in M cannot be tangent to ξ . However many one-dimensional manifolds tangent to ξ exist, and they are said to be Legendrian. Namely a Legendrian knot in M is a map $\gamma : S^1 \hookrightarrow M$ such that $\forall s \in S^1, T_s \gamma \subset \xi (\Leftrightarrow \gamma^* \alpha = 0)$. Two Legendrian knots are Legendrian isotopic if there is an isotopy H between them such that $H(\cdot, t)$ is a Legendrian knot for all t . To a Legendrian knot one can associate three classical invariants:

The topological (or smooth) type of the knot.

The Thurston-Bennequin number of $K = \gamma(S^1)$. It comes from a trivialization of the tubular neighborhood of K given as follow: first take a vector field along K inside ξ transverse to TK which gives the positive orientation of ξ and take a vector field along K transverse to contact structure. If K is null-homologous and a Seifert surface Σ is picked then one can associate a number to this trivialization which is the difference with the canonical trivialization given by Σ . Denote this number by $tb(K, [\Sigma])$, where $[\Sigma]$ denotes

the homology class of Σ in $H_2(M, K)$.

The rotation number of K . Again assume that K is null-homologous and pick a Seifert surface Σ for K . Then the rotation number is the relative Euler class of ξ with respect to the tangent space to γ , $r(K, [\Sigma]) = e(\xi|_{\Sigma}, TK) \in H^2(\Sigma, \partial\Sigma)$ (notice that the definition depends on an orientation of K). The Euler class can, in fact, be replaced by the first Chern class since $d\alpha|_{\xi}$ is a symplectic form on ξ which gives the existence of a unique (up to homotopy) almost-complex structure on ξ compatible with $d\alpha$.

It is easy to check that these three invariants are well defined up to Legendrian isotopy. However it is by now well-known that they don't classify Legendrian knots: using powerful invariants such as Chekanov-Eliashberg homology, see [3], one can exhibit non-isotopic Legendrian knots with the same topological type, Thurston-Bennequin and rotations numbers. On the other hand, it has also been shown that certain restricted classes of knots classified up to Legendrian isotopy by these three classical invariants. One calls such knots *simple* Legendrian knots (see for example [7] where it is shown that the trivial knot is *simple* and [8] for torus knots and figure eight knot). Their classification up to Legendrian isotopy is therefore completely determined by the smooth isotopy classification and easily computed algebraic topology data.

In this paper we are interested in a new relation on the set of Legendrian knots called *Lagrangian concordance*. This relation is analogous to the notion of smooth concordance for knots in 3-manifolds, but the additional structure coming from the contact geometry is now taken into account. Namely we consider a smooth concordance such that the cylinder defining it is a Lagrangian submanifold in the symplectisation of M (Section 3). The symplectisation of a contact manifold (M, ξ) with a globally defined contact form α is identified with $M \times \mathbb{R}$ endowed with the symplectic form $\omega = d(e^t \alpha)$. Much of contact geometry can be reformulated in terms of $\mathbb{R}$ -invariant (or equivariant) symplectic geometry. For instance Legendrian submanifolds of M are in bijection with $\mathbb{R}$ -invariant Lagrangian submanifolds of $M \times \mathbb{R}$, which motivated our definition of a Lagrangian concordance between Legendrian knots. In the present paper we first prove that this construction indeed yields an equivalence relation on the set of Legendrian isotopy classes of knots. We moreover study algebraic properties of Lagrangian concordance and show that the classical Legendrian invariants $tb(\gamma, [\Sigma])$ and $r(\gamma, [\Sigma])$ are in fact Lagrangian concordance invariants (section 5). So that the analogue of classical invariants for our relation still are the Thurston-Bennequin, the rotation number and the topological invariant is now the smooth concordance type of the knot.

We also completely describe the Lagrangian immersion problem with Legendrian boundary conditions in $M \times \mathbb{R}$ by a careful application of the

Gromov-Lees theorem (section 4). We moreover look at the more general notion of Lagrangian cobordism between Legendrian knots in section 6. Using the Lisca-Matic inequality, we are able to give a contact topology proof of Thom conjecture for algebraic knots (section 7). Finally, we conclude with a few remarks about the geometric aspects of Lagrangian concordance.

Acknowledgment. This work makes up part of my Université du Québec à Montréal PhD thesis under the supervision of Olivier Collin who I warmly thank for many helpful comments and discussions. I also wish to thank Paolo Ghiggini and Tamás Kálmán for inspiring conversations, and Tobias Ekholm for pointing out another proof of theorem 6.4.

2. BASICS OF LEGENDRIAN KNOT THEORY

We first fix the notations we will use throughout the paper.

The element s will always refer to a parameter in $S^1 = \mathbb{R}/2\pi\mathbb{Z}$, while t will be a real parameter. So we assume that our cylinder are parametrised by $\{(s, t) | s \in \mathbb{R}/2\pi\mathbb{Z}, t \in \mathbb{R}\}$.

The standard contact structure ξ_0 on $S^3 = \partial D^4 \subset \mathbb{C}^2 (\simeq \mathbb{H})$ will be the one defined by the complex tangencies $\xi_{0,p} = T_p S^3 \cup i(T_p S^3)$. However, in order to simplify notation we will sometimes used $\xi_{0,p} = T_p S^3 \cup j(T_p S^3)$ we will refer the first description as the i-convex contact structure and the second as the j-convex one. These two contact structures are obviously contactomorphic.

If (M, ξ) is a contact manifold with a contact form α we denote by $(M \times \mathbb{R}, \omega)$ its symplectisation, i.e. $\omega = d(e^t \alpha)$. Since ξ is a symplectic vector bundle it admits a compatible complex structure (we always denote by J) which extends to $T(M \times \mathbb{R})$ by setting

$$J \frac{\partial}{\partial t} = R_\alpha$$

Where R_α is the Reeb vector field ($\alpha(R_\alpha) = 1$ and $d\alpha(R_\alpha, \cdot) \equiv 0$). It follows from this remarks that every bundle we consider admits some euclidian (resp. Hermitian) metric. We assume trivializations are orthonormal (resp hermitian).

We let $\langle \cdots \rangle_{\mathbb{C}} = \text{span}_{\mathbb{C}}(\cdots)$, be the complex span of the given vectors and $\langle \cdots \rangle = \text{span}_{\mathbb{R}}(\cdots)$ the real span.

2.1. Legendrian knot in $\mathbb{R}^3$. Through this section the ambient contact manifold will be $\mathbb{R}^3$ together with the standard contact structure defined by $\alpha = dz - ydx$. Associated to a Legendrian knot $\gamma : S^1 \hookrightarrow \mathbb{R}^3$ (with parametrisation $(x(s), y(s), z(s))$) there are two projections: The front projection $\Pi : \mathbb{R}^3 \rightarrow \mathbb{R}_{\langle x, z \rangle}$ and the Lagrangian projection $\pi : \mathbb{R}^3 \rightarrow \mathbb{R}_{\langle x, y \rangle}$ (the name Lagrangian comes from the fact that Legendrian knots project to exact Lagrangian submanifold of $\mathbb{R}^2$).

Although the Lagrangian projection has more geometrical meaning and it can be really useful for some problems, we won't use it here, so we will

only discuss the front projection. Given a closed immersed curve in $\mathbb{R}^2$ with extra data at intersection point to determine which arc crosses over the other one, there is clear obstruction for this diagram to be the projection of a Legendrian knot. From the equation $z'(s) - y(s)x'(s) = 0$ we conclude that

$$y(s) = \frac{z'(s)}{x'(s)},$$

so that there is no vertical tangency to the front projection (we will see cusps instead) and the arc with the smallest slope goes under at an intersection point. On the other hand any diagram satisfying these conditions comes from a Legendrian knot by setting $y(s) = \frac{z'(s)}{x'(s)}$ away from cusps and continuously prolonging it at cusps (sometimes we have to add an open interval where $x'(s) = 0$ to do so). Any Legendrian knot can be isotoped (through Legendrian embeddings) to a Legendrian knot having admissible front projection (meaning transverse self-intersection).

Using this generic projection we can easily compute the Thurston-Bennequin invariant and rotation numbers of K :

$$tb(K) = \text{writhe}(\Pi(K)) - \frac{1}{2}(\text{number of cusps in } \Pi(K))$$

and

$$r(\gamma) = \frac{1}{2}(D - U)$$

where D is the number of downward cusps and U the number of upward cusps (recall K has to be oriented to define the rotation number). Two admissible diagrams will describe Legendrian isotopic knots if and only if they differ by ambient isotopy and a finite sequence of Legendrian Reidemeister moves described by figure 1 (see [17]).

So we can reduce the study of Legendrian knots in $\mathbb{R}^3$ to the study of admissible diagrams up to Legendrian Reidemeister moves. Obviously the combinatorics of such diagrams remains a really difficult problem to solve even if it is easy to formulate.

The contact structure induced on $\mathbb{R}^3$ by removing a point to (S^3, ξ_0) is contactomorphic to the standard one and so everything we said holds for knots in S^3 since we can always assume that any isotopy misses a point in S^3 .

Any Legendrian knot has a standard neighborhood contactomorphic to $N = \mathbb{R}/\mathbb{Z} \times D_\epsilon^2$, for sufficiently small ϵ , with the contact structure given by $dz - ydx$. The front and Lagrangian projections have codomain $\mathbb{R}/\mathbb{Z} \times (-\epsilon, \epsilon)$ which we will draw as a square with the lefthand side identified to righthand side. As the contact structure is locally the same as the one given at the beginning of this section, so everything we said about diagrams still holds, although we have to check that diagrams with slope greater than ϵ are never drawn.

In the next section we will need a description of Legendrian isotopies which stay inside this standard neighborhood, so we propose to discuss this




FIGURE 1. Legendrian Reidemeister moves

here. Denote by K_0 the zero section of this neighborhood and let K be another Legendrian knot in N Legendrian isotopic (in N) to K_0 . Then the degree of the projection of N onto K_0 restricted to K has to be equal to 1. Now an admissible diagram whose projection on K_0 has degree 1 will describe a Legendrian knot isotopic to K_0 if and only if it differs by the same Legendrian Reidemeister moves, since this can be achieved through diagrams having arbitrarily small slopes so as to stay in N .

2.2. The classical invariants. In this section we outline various methods that will be used throughout the article for computing the rotation number and Thurston-Bennequin invariant for Legendrian knots. Let $\gamma_0 : S^1 \rightarrow (M, \xi)$ be a Legendrian knot denote $K_0 = \gamma_0(S^1)$. We identify S^1 with $\mathbb{R}/2\pi\mathbb{Z}$ and suppose K_0 oriented by this parametrisation. The number $tb(K_0)$ will not depend on this parametrisation, but $r(K_0)$ will.

We first consider the Thurston-Bennequin invariant. As it is the homotopy class of the trivialization of the normal bundle $\mathcal{N}(K_0)$ of K_0 given by $tb = (J(\frac{\partial}{\partial s}), R_\alpha)$, it follows that (K_0, tb) is a framed submanifold of M of codimension 2. Via the Thom-Pontryagin construction, it corresponds to a map $h : M \rightarrow S^2$. Suppose now that K_0 is null-homologous and that a Seifert surface Σ for K_0 is fixed. The surface Σ gives an orthogonal trivialization of $\nu(K_0)$ and the difference between this one and tb is thus an element of $\pi_1(SO(2)) = \mathbb{Z}$. We can therefore assign to tb and the relative homology class of Σ an integer which we denote $tb(K_0, [\Sigma])$. The choice of Σ gives a cobordism of K_0 with the trivial knot, so there is a map h' homotopic to h which factors through the fundamental map $[M] : M \rightarrow S^3$. Consequently the homotopy type of h' is characterized by a homotopy class of maps from $S^3 \rightarrow S^2$. Now recall that the free homotopy group $[S^3, S^2]$ is

isomorphic to $\mathbb{Z}$ (the isomorphism is given by the Hopf fibration), therefore h' is characterized by this integer and we claim the following:

Proposition 2.1. *Let $n \in \mathbb{Z}$ be the integer associated to tb and $[\Sigma]$ as above then $tb(K_0, [\Sigma]) = -n$*

Proof We first notice that in the case of the trivial Legendrian knot $K_0 = \{z_2 = 0\}$ in $S^3 = \{(z_1, z_2) \in \mathbb{C}^2 \mid |z_1|^2 + |z_2|^2 = 1\}$ with the contact structure induced by the j -complex tangencies, then tb is $((ie^{i\theta}, 0), (je^{i\theta}, 0))$ which is the trivialization induced by the Hopf map. In this particular case $tb(K_0) = -1$ (by a direct computation or by section 6). So the proposition is verified in that case.

Consider now the general case where $tb(K) = n$. Choose a cobordism from K to K_0 . Since $tb(K) = n$, the extension of the trivialization to the cobordism gives a trivialization on K_0 which is $-n$ times the one given by $tb(K_0)$. The Thom-Pontryagin map is thus $-n$ times the Thom-Pontryagin map associated to $tb(K_0)$, which completes the proof. ■

Corollary 2.2. *The Thurston-Bennequin number of a Legendrian knot in S^3 is completely determined by the Thom map associated to the trivialization given by $tb(K)$.*

Consider now the case of the rotation number of K_0 . We recall that this number is defined by

$$r(K_0, [\Sigma]) = c_1(\xi|_{\Sigma}, \tau),$$

where the relative Chern class can be defined as follows. Consider the trivial complex line bundle $D^2 \times \mathbb{C} \rightarrow D^2$ so that using the trivialization $\tau = \langle \frac{\partial}{\partial s} \rangle$ of the complex line bundle $\xi|_{K_0}$, one can construct a bundle ξ' over $\Sigma' = \Sigma \cup D^2$. We set $c_1(\xi|_{\Sigma}, \tau) = c_1(\xi')$ using the isomorphism $H^2(\Sigma, \partial\Sigma) \simeq H^2(\Sigma') \simeq \mathbb{Z}$.

Furthermore $\xi|_{\Sigma}$ is a complex line bundle over Σ which has the homotopy type of a wedge of circles, hence $\xi|_{\Sigma}$ is trivializable over Σ . Denote such an hermitian trivialization by ν . Then $\nu|_{K_0}$ is a trivialization of ξ along K_0 (notice that since K_0 represents a product of commutators in $\pi_1(\Sigma, x_0)$ and since $\pi_1(U(1), Id)$ is abelian, this trivialization doesn't depend on ν). With respect to this trivialization, τ becomes a loop in $U(1)$ and the homotopy type of this loop in $\pi_1(U(1), Id) \simeq \mathbb{Z}$ is exactly the rotation number.

Example. Consider $S^3 = \partial D^4$ with its i -convex structure and $K_0 : [0, 2\pi] \rightarrow S^3$ a Legendrian knot. We have

$$\xi_{(z_1, z_2)} = \langle -z_2 \frac{\partial}{\partial z_1} + z_1 \frac{\partial}{\partial z_2} \rangle$$

hence ξ_0 is already trivialized over S^3 . So we can chose ν to be this trivialization restricted to Σ . It follows that

$$\tau = \langle e^{i\theta(s)}(-z_2 \frac{\partial}{\partial z_1} + z_1 \frac{\partial}{\partial z_2}) \rangle,$$

and therefore

$$r(K_0) = \frac{1}{2\pi} \int_{S^1} d\theta.$$

There is a third way to define the rotation number in terms of symplectic geometry. Consider in the symplectisation of M the trivial cylinder $C_0 = K_0 \times \mathbb{R}$. At any point of M the (symplectic) tangent space splits as

$$T_p M = \langle \xi_p \rangle \oplus \langle R_\alpha, \frac{\partial}{\partial t} \rangle.$$

This splitting is complex as well as symplectic as it can easily be checked. So we may also trivialize $TM|_\Sigma$ using ν . Consider K_0 as a loop on the Lagrangian cylinder C_0 so that one can interpret, via our trivialization, the loop $T_{K_0(s)}C_0$ as a loop of Lagrangian planes in $\mathbb{C}^2$. One can consequently associate to this loop its Maslov index $\mu(K_0, \Sigma)$ (this loop doesn't depend on ν for the same reason as before).

First recall the general definition of the Maslov index of a contractible loop on a Lagrangian submanifold, for which a good discussion can be found in [18]. Inside the standard symplectic vector space $(\mathbb{C}^n, \omega_0)$, consider $\Lambda(n)$ to be the set of Lagrangian subspaces of $\mathbb{C}^n$, that is,

$$\Lambda(n) = \{V \subset \mathbb{C}^n \mid \dim(V) = n \text{ and } \omega_0|_V = 0\}.$$

Now fix an element V_0 of $\Lambda(n)$ and define the Maslov class to be

$$MC = \{V \subset \Lambda(n) \mid V \cap V_0 \neq \{0\}\}.$$

This is a codimension 1 algebraic variety with singularities corresponding to the set of Lagrangian subspaces whose intersection with V_0 has dimension greater than one. To define the Maslov index we need to give a transverse orientation to MC and this may be achieved in the following way. Any Lagrangian subspace V of $\mathbb{C}^n$ which is transversal to $V_0^\perp$ can be seen as the graph of $dQ \in V_0^*$, where Q is a quadratic form over V_0 . If the intersection with MC increases the signature, the intersection is positive otherwise it is negative. Now any loop $\gamma : S^1 \rightarrow \Lambda(n)$ can be arranged to be transversal to MC so the Maslov index of γ is defined to be $\mu(\gamma) = |\gamma \cdot MC|$.

Remark 2.3. *In fact one should notice that the composite isomorphism*

$$\pi_1(\Lambda(n)) \simeq H^1(\Lambda(n)) \simeq \mathbb{Z}$$

precisely arises from the Maslov index.

In our case, since the loop of Lagrangian planes is given by

$$\gamma(s) = \langle e^{i\theta(s)}(-z_2 \frac{\partial}{\partial z_1} + z_1 \frac{\partial}{\partial z_2}), \frac{\partial}{\partial t} \rangle,$$

things are vastly simplified. Choosing the plane V_0 to be given as

$$V_0 = \langle (-z_2 \frac{\partial}{\partial z_1} + z_1 \frac{\partial}{\partial z_2}), \frac{\partial}{\partial t} + R_\alpha \rangle,$$

We get that intersection point with the Maslov-Class arise when $\theta(s) = 0 \bmod \pi$ and the quadratic form is

$$Q(s) = \tan \theta(s) x^2 + y^2$$

near these intersection points. Hence intersections are positive when $\theta'(s) > 0$ and negative when $\theta'(s) < 0$ (note that the transversality condition is achieved assuming $\theta'(s) \neq 0$ at intersection points).

So we obtain the formula

$$\mu(\gamma) = 2 \int_{S^1} d\theta$$

and hence $\mu(\gamma) = 2r(K_0)$, so that $\mu(K_0, \Sigma) = 2r(K_0, [\Sigma])$.

3. LAGRANGIAN CONCORDANCE AND ITS RELATION TO LEGENDRIAN ISOTOPY

3.1. Definition of Lagrangian concordance. Let M be a smooth oriented 3-manifold, ξ a positive contact structure and $(Y, \omega) \cong (M \times \mathbb{R}, d(e^t \alpha))$ be the symplectisation of M .

Definition 3.1. If $K_0, K_1 : V \hookrightarrow M$ be two Legendrian submanifolds of M , we say that K_0 is Lagrangian concordant to K_1 if there exists a Lagrangian cylinder $C : V \times \mathbb{R} \hookrightarrow Y$ satisfying:

$\exists T > 0$ such that $C|_{(-\infty, -T)} = K_0 \times (-\infty, -T)$ and $C|_{(T, \infty)} = K_1 \times (T, \infty)$.




FIGURE 2. A Lagrangian concordance

The previous definition is motivated by the following. Any $\mathbb{R}$ -invariant Lagrangian submanifold of Y projects to a Legendrian submanifold of M , and any Legendrian submanifold will lift to an $\mathbb{R}$ -invariant Lagrangian submanifold. In particular any Legendrian submanifold will be Lagrangian

concordant to itself. However for the theory of Lagrangian concordance to be more intimately related to Legendrian knot theory, we want a relation up to Legendrian isotopy rather than a relation on the Legendrian submanifolds themselves. For this we have to prove that any Legendrian isotopy in the contact manifold M gives rise to a Lagrangian cylinder in the symplectisation Y . The proof of this fact is the main goal of this section.

But first some remarks about the differences between the Lagrangian concordance and the topological (smooth) concordance are in order.

Remark 3.2. *In the case of a topological concordance, the condition of symmetry needed to obtain an equivalence relation is automatic, by simply reverting the t parameter in the cylinder embedding defining the concordance. In our case, this diffeomorphism $\phi : Y \rightarrow Y$ sending (x, t) to $(x, -t)$ is not a symplectomorphism ($\phi^*(de^t\alpha) = de^{-t}\alpha$). Therefore it is not automatic that K_0 being Lagrangian concordant to K_1 implies K_1 to be Lagrangian concordant to K_0 .*

Remark 3.3. *On the symplectisation Y , the vector field $\frac{\partial}{\partial t}$ expands the symplectic form ω , so that any translation of a Lagrangian submanifold along this vector field will remain Lagrangian. This allows us to prove that the concordance relation is transitive. We can therefore consider this relation to be more like a partial order on set of the isotopy classes of Legendrian submanifolds. We'll denote this partial ordering $K_0 \prec K_1$ (or $K_0 \prec_C K_1$ if the cylinder C has to be specified).*

3.2. Main technical results. This sub-section is devoted to the proof that the notion of Lagrangian concordance is well defined on the set of isotopy classes of Legendrian submanifolds. The main difficulty is the fact the graph of a Legendrian isotopy is not a Lagrangian cylinder in general. Conversely a Lagrangian cylinder which is the graph of a (smooth) isotopy may not be the graph of a Legendrian isotopy.

Let us first recall some facts about standard contact and symplectic structures, as well as Lagrangian and Legendrian submanifolds. Consider on the cotangent bundle of a manifold, T^*M , the standard Liouville form θ which is the unique form satisfying

$$\theta_\lambda(X) = \pi^*(\lambda)_\lambda(X) \quad \forall \lambda \in T^*M, X \in T_\lambda(T^*M)$$

where π is the projection $T^*M \rightarrow M$. In local coordinates $\theta = \sum_{i=1}^n p_i dq_i$. The differential of θ gives the standard symplectic form ω_0 on T^*M . The 1-form $\alpha = dt - \theta$ on the first jet space of M ($J^1(M) \cong T^*M \times \mathbb{R}$) is the standard contact form on $J^1(M)$. One of the important features of Lagrangian (respectively Legendrian) submanifolds M is that they admit standard Darboux-like neighborhood symplectomorphic (respectively contactomorphic) to a neighborhood of the zero section of M inside T^*M (respectively $J^1(M)$) (see [9] for a detailed proof). Through this section, U will denote the standard neighborhood of a Legendrian submanifold in M and V the one of a Lagrangian submanifold of Y . In [9] one can find a

proof of the classical fact that any isotopy K_t of compact Legendrian submanifolds can be realized as ambient isotopy i.e. there exists a family f_t of contactomorphism such that $f_t(K_0) = K_t$.

Theorem 3.4. *Let K_0 and K_1 be two Legendrian submanifolds of M and let $H : V \times I \rightarrow M$ be a Legendrian isotopy between K_0 and K_1 . Then there exists C such that $K_0 \prec_C K_1$. Moreover C can be chosen arbitrarily $(C^0\text{-})$ close to the graph $\Gamma(H)$ of H .*

Proof First assume that we have decomposed our interval into small intervals $(t, t + \epsilon)$, such that for each of these the isotopy sits inside U and its graph sits inside V . Also assume that we perturbed the Legendrian isotopy such that on each interval there is an arc I' inside S^1 which is fixed. We will piecewise construct our Lagrangian cylinder by considering each part of the isotopy as a full isotopy and then glue all the cylinders together to get a final cylinder realizing the isotopy. Now $K_1 \times I$ is a Lagrangian submanifold of V and we would like to consider it as the graph of a 1-form α over $K_0 \times I$. In order to do this, we have to see that the projection $p : V \rightarrow K_0 \times I$ is injective when restricted to $K_1 \times I$. Or equivalently to show that the projection $p' : U \rightarrow K_0$ restricted to K_1 is injective. Under such conditions, we have chosen ϵ small enough the projection is injective and therefore $K_1 \times I$ is the graph of α over $K_0 \times I$. As $K_1 \times I$ is Lagrangian the 1-form α is closed. On the complement $I'' \times I$ of $I' \times I$, the form α is exact, that is $\alpha = df$. Now choose a function h on $I'' \times I$ which is equal to zero nearby $0 \in I$ and is equal to 1 nearby $1 \in I$. The graph of the form α' which is equal to zero on $I' \times I$ and equal to $d(hg)$ on $I'' \times I$ is then, by construction, a Lagrangian cylinder between K_0 and K_1 .

Let us return to the injectivity of the maps p and p' as above. First notice that the degree of $p'|_{K_1}$ is equal to 1 since the isotopy lies inside U . Then the non-injectivity of p' would give the existence of cusps on the front projection of K_1 (i.e the projection along the y-axis). The only way such cusps can possibly occur through a Legendrian isotopy is when a Reidemeister move of type 1 is performed. If a Legendrian Reidemeister move occurs then we must show that we can decompose the isotopy into smaller ones such that the projection are always injective. Denote f_t the smooth family of contactomorphisms such that $f_t(K_0) = K_t$. Let t_0 be the smallest t such that the above projection is non-injective and $t_n < t_0$ converging to t_0 . Denote U_t the standard neighborhood of γ_t and π_t the associated projection. Suppose that $\pi_t|_{K_{t_0}}$ is never injective. This implies that $\pi_0|_{f_{t_n}^{-1}(K_{t_0})}$ is non-injective, and so the associated projection differs from a type 1 Legendrian Reidemeister move. However this is impossible since $f_{t_n}^{-1}(K_{t_0})$ converges smoothly to K_0 . So we can cut the isotopy such that the projections are always injective and this completes the proof. ■

Although we do not have a unique way to construct the cylinder mentioned in the proof of the last theorem, we can say the following. Any two such cylinders as constructed in the proof satisfy the following: one of them sits inside the standard neighborhood of the other one as the graph of closed 1-form. It follows that one can isotope one into the other through a Lagrangian cylinder. Hence our construction is unique if one works with Lagrangian cylinders up to Lagrangian isotopy (the natural analogue in the symplectisation of Legendrian submanifolds up to Legendrian isotopies). Also, by taking ϵ arbitrarily small in the proof, one obtains a cylinder which is arbitrarily C^0 -close to the graph of the Legendrian isotopy. However, since we have no a priori control over the function h used, it is not clear we can actually recover the original isotopy simply from the cylinder data. We ask the following:

Question: Let C_0 and C_1 be two Lagrangian cylinders constructed as above from two Legendrian isotopy H_0 and H_1 . Does the equivalence of C_0 and C_1 up to a Lagrangian isotopy imply that H_0 and H_1 are equivalent through Legendrian isotopies?

4. THE IMMERSION PROBLEM, GROMOV-LEES THEOREM

It is well-known that the study of Lagrangian immersions is easier than the study of Lagrangian embeddings, since the former satisfy the h-principle i.e. if all the algebraic-topological conditions for Lagrangian immersions are satisfied then one can homotope any immersion to a Lagrangian one. We apply such ideas here to obtain a sufficient condition for the existence of an immersed Lagrangian cylinder between smoothly concordant Legendrian knots.

All the terminology in this section come from the general h-principle theory we took from [5], it is also the principal reference for the theorem of Gromov-Lees in its full generality.

Let N be a smooth manifold of dimension n and $(W, \omega = d\theta)$ be an exact symplectic manifold of dimension $2n$. A bundle map $F = (f, g)$ from $T^{\mathbb{C}}(N)$ to TW is called a *formal Lagrangian immersion* of N in W if it is a complex isomorphism on each fiber. If $g = df^{\mathbb{C}}$ and f is an exact Lagrangian immersion ($f^*\theta = dh$) such F will be called *holonomic*. On an open neighborhood of a sub-simplicial complex $A \subset N$, we say that F is holonomic near A if the map g is equal to df for f an exact Lagrangian immersion.

Such definitions are motivated by the following. Let $f : N \rightarrow W$ be a Lagrangian immersion. The map $df : TN \rightarrow TW$ can be complexified to $df^{\mathbb{C}} : TN^{\mathbb{C}} \rightarrow TW$ by setting

$$df^{\mathbb{C}}((a + ib)v) = adf(v) + bJ(df(v)).$$

Since N is Lagrangian, this map is an isomorphism on the fiber so that $F = (df^{\mathbb{C}}, f)$ is a formal Lagrangian immersion. Furthermore these conditions are the only algebraic conditions for a having a Lagrangian immersion: the condition on the homology class of ω being always fulfilled since we assumed that W was exact.

Again, using the fact that the manifold (W, ω) is exact, we can endow $W \times \mathbb{R}$ with a contact structure defined by the contact form $dt - \theta$. There is a one-to-one correspondence between exact Lagrangian immersions and Legendrian submanifolds of $M \times \mathbb{R}$ considered up to $\mathbb{R}$ -translation. The problem of finding a homotopy to a Lagrangian immersion is therefore reduced to Legendrian approximation problem. For our purposes we shall need a stronger condition though, since we want the homotopy to be fixed on a subspace of N . We now state Gromov-Lees theorem:

Theorem 4.1. (Gromov-Lees [15], [5]) *Let (N, A) be a couple where $A \subset N$ is a sub-simplicial complex of N and suppose that there is a formal Lagrangian immersion from $T^{\mathbb{C}}(N)$ to TW which is holonomic near A . Suppose moreover that $[f^*(\omega)] = 0 \in H^2(N, A)$. Then F can be homotoped relative to A to a holonomic map F_1 .*

We apply the result in our context as follows. Suppose we have an immersion $f : S^1 \times \mathbb{R} \rightarrow S^3 \times \mathbb{R}$ which is the trivial cylinder over K_i at each infinite end and consider $f|_{S^1 \times [-T-\epsilon, T+\epsilon]}$ as a map satisfying the first condition of the Gromov-Lees theorem for $A = \partial(S^1 \times [-T-\epsilon, T+\epsilon])$. Then in order to homotope f to an immersed Lagrangian cylinder we need to investigate properly the topological data. Consider first $f_0 = K_1 \times \mathbb{R}$. The induced complexified map is then:

$$\begin{aligned} F_0 : T^{\mathbb{C}}(S^1 \times \mathbb{R}) &\rightarrow T(\mathbb{C}^2 \setminus \{(0, 0)\}) \\ \frac{\partial}{\partial s} &\rightarrow e^{i\theta} \left(-z_2 \frac{\partial}{\partial z_1} + z_1 \frac{\partial}{\partial z_2} \right) \\ \frac{\partial}{\partial t} &\rightarrow \frac{\partial}{\partial r} \end{aligned}$$

Moreover, the map

$$\left(\frac{\partial}{\partial z_1}, \frac{\partial}{\partial z_2} \right) \mapsto \left(-z_2 \frac{\partial}{\partial z_1} + z_1 \frac{\partial}{\partial z_2}, z_1 \frac{\partial}{\partial z_1} + z_2 \frac{\partial}{\partial z_2} \right)$$

provides an isomorphism

$$T(\mathbb{C}^2 \setminus \{(0, 0)\}) \cong \mathbb{C}^2 \setminus \{(0, 0)\} \times \mathbb{C}^2 \cong \mathbb{C}^2 \setminus \{(0, 0)\} \times \langle \xi, \frac{\partial}{\partial r} \rangle$$

so that the induced bundle map is uniquely characterized (up to homotopy) by

$$\int_{S^1} d\theta = r(K_0).$$

Therefore, to homotope f to a Lagrangian immersion it is sufficient to know that $r(K_0) = r(K_1)$ as this condition ensures that we can extend the bundle map induced by $f|_{\partial S^1 \times [-T-\epsilon, T+\epsilon]}$ to the whole cylinder. Furthermore $[f^*(\omega)]$ clearly vanishes since

$$\int_C \omega = \int_{K_1} e^{T+\epsilon} \alpha - \int_{K_1} e^{-T-\epsilon} \alpha = 0$$

We have consequently proved the following:

Theorem 4.2. *Suppose that K_0 and K_1 are two smoothly concordant Legendrian knot such that $r(K_0) = r(K_1)$ then there exist an immersed exact Lagrangian cylinder between them. ■*

Unlike in the closed case, we shall soon see that there exist some "soft" (meaning algebraic) obstructions for such cylinders to be embedded. It should be noticed that Haskins and Pacini have a similar discussion, in greater generality, without using the notion of rotation number see [11]. Also, we have discussed in detail the case where M is S^3 , but everything done in this section carry through in general, for any contact manifold, once a Seifert surface for the first knot is picked to yield a trivialization of the contact structure ξ along it.

5. INVARIANCE OF CLASSICAL INVARIANTS UNDER LAGRANGIAN CONCORDANCE

This section is devoted to prove that both the Thurston-Bennequin and rotation number are invariant under Lagrangian concordance. It will follow that the notion of Lagrangian concordance is more restrictive than usual (smooth) concordance of knots: concordant smooth knots which are also Legendrian knots with different classical invariants cannot be Lagrangian concordant. While this is satisfying, this also means that there are no classical algebraic obstructions for the non-existence of Lagrangian concordances between Legendrian knots, so to eventually find examples of knots which are not Legendrian isotopic but *are* Lagrangian concordant, one has to consider classes of non-simple Legendrian knots and use more sophisticated contact and symplectic invariants.

Consider first the invariance of the rotation number. let $C : S^1 \times \mathbb{R} \hookrightarrow M \times \mathbb{R}$ be a Lagrangian concordance between K_0 and K_1 . Let Σ_0 be a Seifert surface for K_0 which we consider as living in $M \times \{-T\}$. Also define Σ_1 to be a Seifert surface for K_1 in the same homology class as the projection of $\Sigma_0 \cup C|_{S^1 \times [-T, T]}$ to $M \times \{T\}$. From the end of section 2, we know that $\mu(K_i, \Sigma_i) = 2r(K_i, [\Sigma_i])$ and the cylinder $C|_{S^1 \times [-T, T]}$ provides a homotopy

of the loop of Lagrangian planes γ_i induced by K_i and the trivialization of $T(M \times \mathbb{R})$ on $\Sigma_0 \cup C|_{S^1 \times [-T, T]}$. It follows that we have

$$\mu(K_0, \Sigma_0) = \mu(K_1, \Sigma_0 \cup C|_{S^1 \times [-T, T]}) = \mu(K_1, \Sigma_1).$$

And so we have proved the following (which uses the canonical isomorphism $H_*(M) \simeq H_*(M \times \mathbb{R})$ implicitly).

Theorem 5.1. *Let $K_0 \prec_C K_1$, $\Sigma_0 \hookrightarrow M$ a Seifert surface for K_0 and $\Sigma_1 = \Sigma_0 \cup C$ be a surface obtained by gluing a Lagrangian concordance onto Σ_0 . Then the rotation numbers satisfy $r(K_0, [\Sigma_0]) = r(K_1, [\Sigma_1])$. ■*

We consider now the case of the Thurston-Bennequin invariant. Again let C be a Lagrangian cylinder which provides a Lagrangian concordance between two Legendrian knots K_1 and K_2 . One has that the vector field $(\frac{\partial}{\partial s}, \frac{\partial}{\partial t})$ gives a trivialization of TC . Since C is Lagrangian, the vector fields $(J\frac{\partial}{\partial s}, J\frac{\partial}{\partial t})$ give a trivialization of the normal neighborhood of C . Furthermore this trivialization coincides on both components of the ends with the trivialization given by the Thurston-Bennequin invariant. So we have constructed a framed cobordism between (γ_1, tb_1) and (γ_2, tb_2) . Using the description of the Thurston-Bennequin in section 2, we have proved:

Theorem 5.2. *If $K_0 \prec K_1$ then $tb(K_0) = tb(K_1)$, that is, the Thurston-Bennequin invariant of Legendrian knots is invariant under Lagrangian concordance. ■*

We can therefore conclude that we have the following classical invariants for Lagrangian concordances of Legendrian knots:

- (i) The (smooth) concordance type.
- (ii) The rotation number (using a suitably chosen Seifert surface).
- (ii) The Thurston-Bennequin invariant.

6. REMARKS ABOUT LAGRANGIAN COBORDISM

The question of Lagrangian concordance naturally leads to the question of whether or not a Legendrian knot bounds a Lagrangian surface in a symplectic filling. Let us first study the trivial example which will be relevant in the following section: consider in $D^4 \subset \mathbb{C}^2 \simeq \mathbb{H}$ the disk $D^2 = \{z_1 = 0\}$, which is a holomorphic disk for the standard Kähler structure (namely multiplication by i). If we change the Kähler structure by an orthogonal one (e.g. multiplication by j), this disk turns out to be a Lagrangian one. Now consider $K = \partial D^2 \subset S^3$, a trivial knot in the 3-sphere (actually this a fiber of the Hopf fibration) which turns out to be Legendrian for the contact structure standard contact structure

$$\xi_p = T_p S^3 \cap j(T_p S^3).$$

We will argue below that for this knot

$$r(K) = 0 \text{ and } tb(K) = -1 = TB(\mathcal{L}_0),$$

where $\mathcal{L}_0$ is the smooth isotopy class of the trivial knot.

Going back to the general case, through the discussion X will be a Stein surface with boundary M endowed with the contact structure ξ induced by complex tangencies (which is well-known to be tight) and $\mathcal{L}$ will be the smooth isotopy class of a knot. Suppose that there is an oriented Lagrangian surface $L : \Sigma \hookrightarrow X$ whose boundary is a Legendrian knot $K \in \mathcal{L}$. Then the Lisca & Matic's ([16] and [6] for $X = D^4$) adjunction inequality gives:

$$tb(K) + |r(K)| \leq -\chi(\Sigma) = 2g(\Sigma) - 1.$$

Note that $tb(K)$ and $r(K)$ are numbers associated to Σ the same way as before.

We can use the Gompf surgery description [10] to produce a new Stein manifold diffeomorphic to

$$X(K, tb(K) - 1) = X \sqcup D^2 \times D^2 / \{f(S^1 \times D^2) \equiv N(K)\},$$

where f is the surgery map. The complex structure on $X(K)$ is the one induced by X and $D^2 \times D^2$ as a subset of $\mathbb{R}^2 \oplus i\mathbb{R}^2$. Now $D^2 \times \{0\}$ is a Lagrangian disk which we use to cap off Σ , so that we get a closed Lagrangian surface Σ' inside $X(K)$ (notice that it is smooth since the Maslov indexes of K on Σ and on D^2 are equal to zero, see [14]). Its self-intersection is consequently:

$$\Sigma' \cdot \Sigma' = 2g(\Sigma') - 2 = 2g(\Sigma) - 2.$$

However the surgery description also tells us that:

$$\Sigma' \cdot \Sigma' = tb(K) - 1.$$

Combining the two formulas we therefore get:

$$2g(\Sigma) - 1 = tb(K) \leq 2g(\Sigma) - 1 - |r(K)|.$$

This means that we have proved the following:

Proposition 6.1. *Let Σ be an oriented Lagrangian submanifold of a Stein surface. Suppose that $\partial\Sigma$ is Legendrian submanifold K of ∂X . Then the following holds:*

$$r(K) = 0$$

$$tb(K) = 2g(\Sigma) - 1 = TB(\mathcal{L})$$

Furthermore, if $X \simeq D^4$, then

$$g(\Sigma) = g_s(\mathcal{L}),$$

Where $\mathcal{L}$ is the smooth isotopy type of K and $g_s(\mathcal{L})$ is the 4-ball genus of $\mathcal{L}$.

■

Intuitively, one can therefore think of Legendrian knots bounding Lagrangian surfaces as being maximal for the Thurston-Bennequin invariant ans, above all, for the partial ordering given by Lagrangian concordance.

Remark 6.2. *One knows some knots yielding examples where the Lisca-Matic inequality is not sharp (e.g. negative torus knots, connected sum of torus knot ...). Consequently, by the previous proposition, such knots cannot bound Lagrangian surfaces in D^4 .*

Remark 6.3. *By carrying out the analysis done in section 4, we arrive at the conclusion that a Legendrian knot bounds an immersed Lagrangian surface in D^4 if and only if it has rotation number equal to zero (compare [11]).*

In the same spirit of this section and from the observation we made in section 4 and 5 we have the following:

Theorem 6.4. *Suppose Σ is an oriented embedded Lagrangian surface with two punctures such that around one puncture $\Sigma = K_0 \times (-\infty, -T)$ and around the other $\Sigma = K_1 \times (T, \infty)$ then $tb(K_1) - tb(K_0) = 2g(\Sigma)$*

Proof On Σ take the vector field $-\nabla f$ where f is the height function shown in figure 3. It has $2g$ index -1 critical points. Hence any nowhere vanishing vector field extending $\frac{\partial}{\partial t}$ around the first puncture will have winding number $-2g$ with respect to $\frac{\partial}{\partial t}$ around the second one. (JX, Y) (where Y is a positive orthogonal to JX in $N(\Sigma)$) is then a framed cobordism from $(K_0, tb(K_0))$ to (K_1, ν) where ν differs from $tb(K_1)$ by $2g$ twists. ■




FIGURE 3. Height function on Σ

7. APPLICATIONS AND REMARKS

In this final section we provide some examples of Lagrangian surfaces bounding Legendrian knots and we use section 6 to give an alternative proof of the local Thom conjecture about the 4-ball genus of algebraic knots (a particular case being the Milnor conjecture determining the unknotting number of a torus knot). In the latter part of the section, we make a few more remarks about Lagrangian concordances of Legendrian knots, work to be done in the future by the author.

7.1. Algebraic Legendrian knots. Let $P : \mathbb{C}^2 \rightarrow \mathbb{C}$ be a polynomial such that $P(0,0) = 0$ and 0 is a critical value of P with $(0,0)$ as unique critical point. The intersection

$$K = P^{-1}(0) \cap S_\epsilon^3,$$

with a small three-sphere about the origin is a codimension 2 submanifold, and if it is a knot one says that this knot is *algebraic*. The manifold $S_\epsilon^3 - K$ may be given the structure of a fibration over S^1 via the Milnor construction

$$f(z_1, z_2) = \frac{P(z_1, z_2)}{|P(z_1, z_2)|},$$

and the same holds for $D_\epsilon^4 - P^{-1}(\delta)$, where $\delta > 0$ is small enough. The fiber of the first fibration is called the Milnor fiber of the singularity and is a Seifert surface for K . One way to formulate the local Thom conjecture is to say that this Seifert surface is genus minimizing in D^4 . Notice that the genus of this fiber is given as the genus of $P^{-1}(\delta)$ for any regular value δ of P .

The aim of this section is to show that we can find a canonical Legendrian representative of an algebraic knot together with a Lagrangian surface bounded by it. On $\mathbb{C}^2 \simeq \mathbb{H}$ we will consider the Kähler structure given by multiplication by j (instead of i). Any embedding of D^4 such that its boundary is transversal to the vector field $\frac{\partial}{\partial r}$ will carry a Stein manifold structure induced by the Kähler structure given above.

Consider δ a regular value of P and $P|_{S_\epsilon^3}$ for any ϵ sufficiently small. Since the structure induced by j is orthogonal to the one induced by i and $\Sigma = P^{-1}(\delta)$ is a complex curve we have that it is a Lagrangian surface for the symplectic structure we have chosen. We consequently wish to find a convex embedding of the 3-sphere such that its intersection with Σ is Legendrian. Let $K = \Sigma \cap S_\epsilon^3$ and choose a neighborhood N of K in D^4 diffeomorphic to $S^1 \times D^2 \times I$ such that we can write

$$N \cap S_\epsilon^3 = \{(s, x, y, 0) \in S^1 \times D^2 \times I\},$$

where $\frac{\partial}{\partial r}$ corresponds to $\frac{\partial}{\partial t}$, for t the parameter in the I direction. Since Σ is transversal to S_ϵ^3 , the vector field $i(TK)$ equal, up to rescaling, to $(x(s), y(s), 1)$. Consider the embedding h of $S^1 \times D^2$ in N given by

$$h(s, x, y) = (s, x, y, (1 - x^2 - y^2)^2(-x(s)x - y(s)y)).$$

This embedding is transversal to $\frac{\partial}{\partial t}$ and, on $S^1 \times \{(0,0)\}$, its tangent space is orthogonal to $i(TK)$ and hence it contains $j(TK)$. Furthermore it coincides

with the embedding of $S^1 \times D^2$ on $S^1 \times S^1$, so we can use h to construct a new embedding h' of S^3 into $\mathbb{C}^2$ such that $\Sigma \cap h'(S^3) = K$, $j(TK)$ is tangent to $h'(S^3)$ and $\frac{\partial}{\partial r}$ is transversal to $h'(S^3)$. It follows that the j -complex tangencies form a contact structure isomorphic to ξ_0 on S^3 where we now have that K is Legendrian and bounds a Lagrangian surface in D^4 . Using Proposition 6.1, we have therefore proved:




FIGURE 4. Modification of embedding on $\{s\} \times D^2 \times I$

Theorem 7.1. *Let K_0 be an algebraic knot with Milnor fiber Σ . Then*

- (i) *There exists a convex sphere such that its intersection with Σ is a Legendrian representative K of $\mathcal{L}(K_0)$.*
- (ii) *The Legendrian representative K has maximal Thurston-Bennequin number and trivial rotation number and satisfies $tb(K) = 2g_s(K_0) - 1$.*
- (iii) *The 4-ball genus $g_s(K_0)$ of K_0 is given as $g_s(K_0) = g(\Sigma)$.*

Remark 7.2. *The computation of $TB(\mathcal{L})$ in (ii) is a classical result of Bennequin, see [1]. Part (iii) gives a new proof of the local Thom conjecture first proved by Kronheimer and Mrowka in [13] as we have shown that the Milnor fiber is genus minimizing among all surfaces in D^4 bounded by K .*

7.2. Concluding Remarks. So far we have not been able to find examples of non-trivial Legendrian knot concordances between knots which are known not to be Legendrian isotopic. From a topological point of view, concordance is a much weaker relation than smooth isotopy, but what prevents us, so far, from using this fact in the Legendrian knot setting is that the classical Legendrian knot invariants are concordance invariants as we have proved. We hope to use more sophisticated invariants to explicitly construct families of Legendrian knots which are Lagrangian concordant without being Legendrian isotopic.

Recall that a topological knot type is Legendrian simple if the Legendrian isotopy classes are classified by the Thurston-Bennequin and rotation number. Examples of Legendrian simple knots are given in [8], where it is shown that torus knots and the figure eight knot are simple. From section 5 and 3 we conclude:

Corollary 7.3. *If $\mathcal{L}$ is a Legendrian simple knot type the any two Legendrian representative of $\mathcal{L}$ are Lagrangian concordant iff they are Legendrian isotopic.* ■

There is also an obvious link between Lagrangian Concordance and Legendrian Contact Homology. Following [2] we see that a Lagrangian cylinder between two Legendrian knots could be used to define a map between the algebras $CH(K_0)$ and $CH(K_1)$ (see [4]), we, however, will not give a more detailed description of this map for two reasons. First, we have not computed this map for non-trivial cylinder yet; moreover Tamas Kalman already has in [12] a combinatorial map in Contact Homology for Legendrian isotopies. So before enlarging our current article, we plan to do two things: give a non trivial example of such a map, and hopefully be able to compare this map with the one of [12] when the cylinder is constructed as in 3.

From the result of section 5 and 4 we know that on an immersed Lagrangian cylinder between two Legendrian knots, the difference between the Thurston-Bennequin numbers is an obstruction to suppress the double points of the immersion. Notice that from the construction in section 4 the double points of this immersion arise in pairs with opposite signs, since we started from a smooth concordance. To this kind of double points, one can associate another algebraic invariant; the Maslov index of the pair $\mu(x, y)$. We expect this number to be related to the difference of the Thurston-Bennequin numbers. In the case where we actually have an embedded Lagrangian cylinder between two Legendrian knots and that ones perturbs it to obtain an immersion with two transverse double points, then the Maslov index of this pair of points is equal to 1 (compare [14]). We therefore wish to formulate the following conjecture:

Conjecture 7.4. *Let C be an immersed Lagrangian cylinder constructed as in 4 between to smoothly concordant Legendrian knot. And let $\{x_i, y_i\}, i \in \{1..k\}$ be cancelable pairs of double point together with $u_i \in \pi_2(x_i, y_i)$ some Whitney disks (these exist by the hypothesis that the pairs are cancelable). Then $\sum_{i=1}^k (\mu(x_i, y_i, u_i) - 1) = tb(K_1) - tb(K_2)$*

We now finish the paper proving one last result concerning the behavior of Lagrangian concordance under stabilization. We recall that the stabilization S^+ or S^- of any Legendrian knot K can be define (see [8]) by the operation which consists of exchanging an arc γ of K (in its standard neighborhood) the way described by the following figure:

Now suppose that we have a Lagrangian concordance C between K_0 and K_1 and fix a neighborhood N of C symplectomorphic to the symplectisation of the standard neighborhood of K_0 then replacing $\gamma \times \mathbb{R}$ by the band $S^{(+,-)}(\gamma)$ gives a Lagrangian concordance we denote by $S^{(+,-)}(C)$ between the stabilized knots. hence:




FIGURE 5. Stabilization of Legendrian knot

Proposition 7.5. *Let C be a concordance between K_0 and K_1 then $S^{(+,-)}(C)$ is a concordance between $S^{(+,-)}(K_0)$ and $S^{(+,-)}(K_1)$. ■*

REFERENCES

- [1] Daniel Bennequin. Entrelacements et équations de Pfaff. In *Third Schnepfenried geometry conference, Vol. 1 (Schnepfenried, 1982)*, volume 107 of *Astérisque*, pages 87–161. Soc. Math. France, Paris, 1983.
- [2] Frédéric Bourgeois. Contact homology and homotopy groups of the space of contact structures. *Math. Res. Lett.*, 13(1):71–85, 2006.
- [3] Yuri Chekanov. Differential algebra of Legendrian links. *Invent. Math.*, 150(3):441–483, 2002.
- [4] Tobias Ekholm, John Etnyre, and Michael Sullivan. The contact homology of Legendrian submanifolds in $\mathbb{R}^{2n+1}$. *J. Differential Geom.*, 71(2):177–305, 2005.
- [5] Y. Eliashberg and N. Mishachev. *Introduction to the h-principle*, volume 48 of *Graduate Studies in Mathematics*. American Mathematical Society, Providence, RI, 2002.
- [6] Yakov Eliashberg. Filling by holomorphic discs and its applications. In *Geometry of low-dimensional manifolds, 2 (Durham, 1989)*, volume 151 of *London Math. Soc. Lecture Note Ser.*, pages 45–67. Cambridge Univ. Press, Cambridge, 1990.
- [7] Yakov Eliashberg and Maia Fraser. Classification of topologically trivial Legendrian knots. In *Geometry, topology, and dynamics (Montreal, PQ, 1995)*, volume 15 of *CRM Proc. Lecture Notes*, pages 17–51. Amer. Math. Soc., Providence, RI, 1998.
- [8] John B. Etnyre and Ko Honda. Knots and contact geometry. I. Torus knots and the figure eight knot. *J. Symplectic Geom.*, 1(1):63–120, 2001.
- [9] Hansjörg Geiges. Contact geometry. In *Handbook of differential geometry. Vol. II*, pages 315–382. Elsevier/North-Holland, Amsterdam, 2006.
- [10] Robert E. Gompf. Handlebody construction of Stein surfaces. *Ann. of Math. (2)*, 148(2):619–693, 1998.
- [11] Mark Haskins and Tommaso Pacini. Obstructions to special lagrangian desingularizations, and the lagrangian prescribed boundary problem, 2006.
- [12] Tamás Kálmán. Contact homology and one parameter families of Legendrian knots. *Geom. Topol.*, 9:2013–2078 (electronic), 2005.
- [13] P. B. Kronheimer and T. S. Mrowka. Gauge theory for embedded surfaces. I. *Topology*, 32(4):773–826, 1993.
- [14] François Lalonde. Suppression lagrangienne de points doubles et rigidité symplectique. *J. Differential Geom.*, 36(3):747–764, 1992.
- [15] J. Alexander Lees. On the classification of Lagrange immersions. *Duke Math. J.*, 43(2):217–224, 1976.
- [16] P. Lisca and G. Matić. Stein 4-manifolds with boundary and contact structures. *Topology Appl.*, 88(1-2):55–66, 1998. Symplectic, contact and low-dimensional topology (Athens, GA, 1996).

- [17] Jacek Świątkowski. On the isotopy of Legendrian knots. *Ann. Global Anal. Geom.*, 10(3):195–207, 1992.
- [18] Claude Viterbo. Intersection de sous-variétés lagrangiennes, fonctionnelles d'action et indice des systèmes hamiltoniens. *Bull. Soc. Math. France*, 115(3):361–390, 1987.

UNIVERSITÉ DU QUÉBEC À MONTRÉAL, MONTRÉAL, CANADA, H3C 3P8
E-mail address: `chantrai@math.uqam.ca`